



Government of India  
Ministry of Environment, Forest and Climate Change  
(Issued by the State Environment Impact Assessment  
Authority(SEIAA), Maharashtra)

To,

The Partner  
MS.RACHANA LIFE SPACES & RACHANA DEVELOPERS.  
Rachana House, 1229/B, F.C. Road, Deccan Gymkhana, Pune. -411004

**Subject:** Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/MH/MIS/242225/2021 dated 03 Dec 2021. The particulars of the environmental clearance granted to the project are as below.

- |  |  |
|--|--|
| 1. EC Identification No.                   | EC22B039MH147876   |
| 2. File No.                                | SIA/MH/MIS/242225/2021   |
| 3. Project Type                            | Expansion7   |
| 4. Category                                | B1   |
| 5. Project/Activity including Schedule No. | 8(b) Townships and Area Development projects.  |
| 6. Name of Project                         | "Bella casa"- Residential and Commercial Development by M/s. Rachana Life Spaces & Rachana Developers. |
| 7. Name of Company/Organization            | MS.RACHANA LIFE SPACES & RACHANA DEVELOPERS.   |
| 8. Location of Project                     | Maharashtra  |
| 9. TOR Date                                | N/A  |

The project details along with terms and conditions are appended herewith from page no 2 onwards.

Date: 11/07/2022

(e-signed)  
Manisha Patankar Mhaiskar  
Member Secretary  
SEIAA - (Maharashtra)

*Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH. Please quote identification number in all future correspondence.*

*This is a computer generated cover page.*

PARIVESH

(Pro-Active and Responsive Facilitation by Interactive,  
and Virtuous Environmental Single-Window Hub)



**STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY**

No. SIA/MH/MIS/242225/2021  
Environment & Climate  
Change Department  
Room No. 217, 2<sup>nd</sup> Floor,  
Mantralaya, Mumbai- 400032.

To  
M/s. Rachana Life Spaces &  
M/s. Rachana Developers,  
S. No. 42/2, 42/43/44(P) & 43/1(P),  
Village - Sus, Taluka Mulshi, Dist.-Pune

**Subject** : Environmental Clearance for Residential and Commercial Development Project "Bella Casa" at S. No. 42/2, 42/43/44(P) & 43/1(P) of village - Sus, Taluka Mulshi, Dist.-Pune by M/s. Rachana Life Spaces & M/s. Rachana Developers

**Reference** : Application no. SIA/MH/MIS/242225/2021

This has reference to your communication on the above-mentioned subject. The proposal was considered by the SEAC-3 in its 140<sup>th</sup> meeting under screening category 8 (b) B1 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 244<sup>th</sup> (Day-3) meeting of State Level Environment Impact Assessment Authority (SEIAA).

2. Brief Information of the project submitted by you is as below:-

Proposal Number	SIA/MH/MIS/242225/2021
Name of Project	Residential and Commercial Development Project "Bella Casa" by M/s. Rachana Life Spaces & M/s. Rachana Developers
Project category	8b (B1)
Type of Institution	Private
Project Proponent	M/s. Rachana Life Spaces & M/s. Rachana Developers
Consultant	Enviro Analysts and Engineers Pvt. Ltd.
Applied for	Environment Clearance- Expansion project
Details of previous EC	Earlier obtained Environmental Clearance vide No. SEIAA-EC-0000002176 dated March 13., 2020 for the construction area 1,67,339.89 m <sup>2</sup>
Location of the project	at S. No. 42/2, 42/43/44(P) & 43/1(P) of village - Sus, Taluka Mulshi, Dist.-Pune, State – Maharashtra.
Latitude and Longitude	18°33'20.37"N, 73°45'38.60"E
Total Plot Area (m2)	63,850.00 m <sup>2</sup>
Deductions (m2)	14,248.76 m <sup>2</sup>
Net Plot area (m2)	49,601.24 m <sup>2</sup>
Proposed FSI area (m2)	84,399.34 m <sup>2</sup>
Proposed non-FSI area (m2)	82,556.03 m <sup>2</sup>

Proposed TBUA (m <sup>2</sup> )	1,66,955.37m <sup>2</sup>																																											
TBUA (m <sup>2</sup> ) approved by Planning Authority till date	FSI : 84,399.34 m <sup>2</sup> Non FSI : 82,556.03 m <sup>2</sup> Total Construction Area : 1,66,955.37 m <sup>2</sup> Sanction No. BMU/Outward No.761/ dated 08/07/2021.																																											
Ground coverage (m <sup>2</sup> ) & %	16540.87 m <sup>2</sup> (33 %)																																											
Total Project Cost (Rs.)	Rs. 238.43 Cr.																																											
CER as per MoEF & CC circular dated 01/05/2018	CER Shall be implemented as a part of EMP as recommended by SEAC/SEIAA as mentioned in OM F. No. 22-65/2017-IA.III dated September 30, 2020 and its clarifications thereof.																																											
Details of Building Configuration: <Please use following legends: Floor = F , Parking = Pk, Podium = Po, Stilt =St, Lower Ground = LG, Upper Ground = UG, Basement = B, Shops = Sh>			Reason for Modification / Change																																									
Existing Configuration	Proposed Configuration		Revision in Proposal																																									
<table border="1"> <thead> <tr> <th>Sr. No</th> <th>Building</th> <th>No. of Floors</th> </tr> </thead> <tbody> <tr> <td>1.a</td> <td>Building A</td> <td>3P + 10</td> </tr> <tr> <td>2</td> <td>Building B</td> <td>4P + 15</td> </tr> <tr> <td>2.a</td> <td>B - Commercial</td> <td>Gr + Mezz. Shops</td> </tr> <tr> <td>3</td> <td>Building C</td> <td>LG + UG + 11</td> </tr> <tr> <td>3.a</td> <td>C - Commercial</td> <td>Ground Shops</td> </tr> </tbody> </table>	Sr. No	Building	No. of Floors	1.a	Building A	3P + 10	2	Building B	4P + 15	2.a	B - Commercial	Gr + Mezz. Shops	3	Building C	LG + UG + 11	3.a	C - Commercial	Ground Shops	<table border="1"> <thead> <tr> <th>Sr. No.</th> <th>Building</th> <th>No. of Floors</th> <th>Number of flats</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td>Basement + Gr.P +</td> <td>103</td> </tr> <tr> <td>1.a</td> <td>Building A</td> <td>3P + 15</td> <td></td> </tr> <tr> <td>2</td> <td>Building B</td> <td>4P + 15</td> <td>90</td> </tr> <tr> <td>2.a</td> <td>B - Commercial</td> <td>Gr + Mezz. Shops</td> <td>05</td> </tr> <tr> <td>3</td> <td>Building C</td> <td>LG + UG + 11</td> <td>65</td> </tr> </tbody> </table>	Sr. No.	Building	No. of Floors	Number of flats			Basement + Gr.P +	103	1.a	Building A	3P + 15		2	Building B	4P + 15	90	2.a	B - Commercial	Gr + Mezz. Shops	05	3	Building C	LG + UG + 11	65	
Sr. No	Building	No. of Floors																																										
1.a	Building A	3P + 10																																										
2	Building B	4P + 15																																										
2.a	B - Commercial	Gr + Mezz. Shops																																										
3	Building C	LG + UG + 11																																										
3.a	C - Commercial	Ground Shops																																										
Sr. No.	Building	No. of Floors	Number of flats																																									
		Basement + Gr.P +	103																																									
1.a	Building A	3P + 15																																										
2	Building B	4P + 15	90																																									
2.a	B - Commercial	Gr + Mezz. Shops	05																																									
3	Building C	LG + UG + 11	65																																									

4	Building D & E	P+07	67	C - Commercial	Ground Shops	07
5	Building F	P+11	64	Building D & E	P+07	67
6	Building G	P+11	43	Building F	P+11	64
7	Building H	P+11	64	Building G	P+11	43
8	Building J	P+11	43	Building H	P+11	64
9	Building K	LG + UG+12	72	Building J	P+11	43
10	Building L	LG + UG +12	72	Building K	LG + UG +12	72
11	Building M	LG + UG +12	72	Building L	LG + UG +12	72
12	Building N1 +N2	4P + 15	120	Building M	LG + UG +12	72
13	Building O	4P + 15	120	Building N1 +N2	5P + 14	112
14	Building Q	P +06	12	Building O	5P + 14	84
15	Bungalow w	P +02	13	shop Bungalows	P +02	1
16	Commercial 1	P + Grd + 03	14	Commercial 1	P + Grd. + 03	10 shops + 27 offices
17	Commercial 2	P+1 st +2nd + 3P +12	2	Commercial 1	P + Grd. + 03	10 shops + 27 offices

				Basement + Gr.P + 1st 2nd 3P + 10FL	2 Show Rooms + 40 offices	
	<b>Total Tenements</b>		16	Commercial 2		
			17	Club House-2	G+01	1
			18	Club House-3	Ground	1
			19	Club House-4	P+02	1
	<b>Total number of tenements</b>		Total Tenements =952 Nos. , 1 Bungalow, 22 Nos. of shops (7 shops in C building. +5 shops in B building + Commercial 1 building 10 shops) + (Commercial 1 building - 27 offices & Commercial 2 buildings (40 offices + 2 show rooms) 67 Nos. of Offices & 2 show rooms +, and 3 Nos. of club houses			Change as per revised proposal
	<b>Water Budget</b>					
	<b>Dry Season (CMD)</b>		<b>Wet Season (CMD)</b>			
	Fresh Water		Fresh Water		471	
	Recycled		Recycled		298	
	Swimming Pool		Swimming Pool		09	
	Flushing		Flushing		250	
	Gardening		Gardening		0	
	Total		Total		721	
	Waste water generation		Waste water generation		649	
	<b>Water Storage Capacity for Firefighting / UGT</b>		<b>Details of UGT:</b> <ul style="list-style-type: none"> <li>• Domestic UG tank Capacity: 650 m<sup>3</sup></li> <li>• Flushing water tank: 403 m<sup>3</sup></li> <li>• Raw Water Tank :162 m<sup>3</sup></li> <li>• Fire Fighting UGT: 300000 Ltr.</li> </ul> Existing + 200000 Ltr for proposed Buildings.			
	<b>Source of water</b>		From Local Authority			
	<b>Rainwater Harvesting (RWH)</b>		Level of the Ground water table:		Pre-Monsoon:15-20 m below Post Monsoon:5-6 m below	
			Size and no of RWH tank(s) and Quantity:		NA	
			Quantity and size of recharge pits:		14 Nos. Existing: 8 Nos. 1.50mx3.0mx1.50	

		m & Proposed : 6 nos. 2.0mx2.0mx2.0m																		
	Details of UGT tanks if any:	<ul style="list-style-type: none"> <li>• Domestic UG tank Capacity: 650 m<sup>3</sup></li> <li>• Flushing water tank: 403 m<sup>3</sup></li> <li>• Raw Water Tank :162 m<sup>3</sup></li> <li>• Fire Fighting UGT: 300000 Ltr. Existing + 200000 Ltr for proposed Buildings.</li> </ul>																		
Sewage and Wastewater	Sewage generation in CMD:	649 m <sup>3</sup> /day																		
	STP technology:	MBBR																		
	Capacity of STP (CMD):	3Nos. (Existing- 1 NO. 285 m <sup>3</sup> /day +Proposed- 1 No. 10 m <sup>3</sup> /day +1 No. 355 m <sup>3</sup> /day (existing 70 m <sup>3</sup> /day capacity STP will be discontinued and merged in proposed STP 355 m <sup>3</sup> /day).																		
Solid Waste Management during Construction Phase	<table border="1"> <thead> <tr> <th>Type</th> <th>Quantity (kg/d)</th> <th>Treatment / disposal</th> </tr> </thead> <tbody> <tr> <td>Dry waste:</td> <td>27</td> <td rowspan="2">Handed over to Authorized vendor</td> </tr> <tr> <td>Wet waste:</td> <td>18</td> </tr> <tr> <td>Construction waste</td> <td>15197.8 3m<sup>3</sup></td> <td>Will be used in backfilling in the building structure &amp; infrastructure work</td> </tr> </tbody> </table>		Type	Quantity (kg/d)	Treatment / disposal	Dry waste:	27	Handed over to Authorized vendor	Wet waste:	18	Construction waste	15197.8 3m <sup>3</sup>	Will be used in backfilling in the building structure & infrastructure work							
	Type	Quantity (kg/d)	Treatment / disposal																	
	Dry waste:	27	Handed over to Authorized vendor																	
	Wet waste:	18																		
Construction waste	15197.8 3m <sup>3</sup>	Will be used in backfilling in the building structure & infrastructure work																		
Solid Waste Management during Operational Phase	<table border="1"> <thead> <tr> <th>Type</th> <th>Quantity (kg/d)</th> <th>Treatment / disposal</th> </tr> </thead> <tbody> <tr> <td>Dry waste:</td> <td>1233</td> <td>Handed over to Authorized Agency</td> </tr> <tr> <td>Wet waste:</td> <td>1616</td> <td>Treated in OWC</td> </tr> <tr> <td>Hazardous waste:</td> <td>NA</td> <td>-</td> </tr> <tr> <td>Biomedical waste</td> <td>NA</td> <td>-</td> </tr> <tr> <td>E-Waste</td> <td>12 kg/yr.</td> <td>Handed over to Authorized Agency</td> </tr> </tbody> </table>		Type	Quantity (kg/d)	Treatment / disposal	Dry waste:	1233	Handed over to Authorized Agency	Wet waste:	1616	Treated in OWC	Hazardous waste:	NA	-	Biomedical waste	NA	-	E-Waste	12 kg/yr.	Handed over to Authorized Agency
	Type	Quantity (kg/d)	Treatment / disposal																	
	Dry waste:	1233	Handed over to Authorized Agency																	
	Wet waste:	1616	Treated in OWC																	
	Hazardous waste:	NA	-																	
	Biomedical waste	NA	-																	
E-Waste	12 kg/yr.	Handed over to Authorized Agency																		

	STP Sludge (dry)	32 kg/day	Used as manure
Green Belt Development	Total RG area (m2):	5835.44	
	Existing trees on plot:	452 Nos.	
	Number of trees to be planted:	286 Nos.	
	Number of trees to be cut:	00	
	Number of trees to be transplanted:	00	
Power requirement:	Source of power supply:	By MSEDCL	
	During Construction Phase (Demand Load):	300 kVA	
	During Operation phase (Connected load):	6023.94 kW	
	During Operation phase (Demand load):	3653.01 kVA	
	Transformer:	Total: 8 Nos. Existing Total 4 Nos. (3 Nos. 630 Kva +1 No. 200 kVA), Proposed Total: 4Nos. of 630 kVA	
	DG set	Total: 6 Nos. Existing: 3 Nos. (160 kVA-1 No., 125kVa-1 No., 82.50 kVa 1 No.) Proposed: 3 Nos. (250 kVA 1 No., 82.5 kVa 1 No., 25 KVA 1No.)	
	Fuel used	Diesel	
Details of Energy saving	<ul style="list-style-type: none"> <li>• Use of CFL in the Common Passages and for general lighting with automatic time controller.</li> <li>• Use of Transformers and Motors of high efficiency.</li> <li>• Solar lights will be used for water heating and area lighting.</li> </ul>	Total saving 9.84 %	

Environmental Management plan budget during Construction phase				Rs. 22.85 Lakhs																
Environmental Management plan Budget during Operation phase	Sr. No.	Particulars	Capital cost (Rs. In Lacs)	O & m cost (Rs. In Lacs)																
	A	COMPLETED & HANDED OVER PHASE																		
	1	Solid waste management-OWC	46.5	4.77																
	2	Waste water management-STP	54.18	13.4																
	3	Energy	36.89	0.75																
	4	RWH system	3.6	0.35																
	5	Landscape	46.62	5.17																
	6	Swimming Pool	27.15	2.65																
	7	Environmental Monitoring	--	5.65																
	A	Total for completed & Handed over phase	214.94	32.74																
	B	PROPOSED PHASE																		
	1	Solid waste management-OWC	16.75	3.16																
	2	Waste water management-STP	105.1	20.62																
	3	Energy	73.55	0.65																
	4	RWH system	2.7	0.25																
	5	Landscape	21.56	2.39																
	6	Swimming Pool	27.6	2.35																
	7	Environmental Monitoring	--	6.77																
	B	Total for Proposed Phase	247.26	36.19																
		A+B	462.2	68.93																
Traffic Management	<table border="1"> <thead> <tr> <th>Type</th> <th>Required as per DCR</th> <th>Actual Provided</th> <th>Area per parking (m2)</th> </tr> </thead> <tbody> <tr> <td>4-Wheeler</td> <td>1196</td> <td>1196</td> <td>Avg. 33.0</td> </tr> <tr> <td>2-Wheeler</td> <td>1759</td> <td>1759</td> <td>Avg. 3.5</td> </tr> <tr> <td>Bicycles</td> <td>1509</td> <td>1509</td> <td>Avg. 1.5</td> </tr> </tbody> </table>				Type	Required as per DCR	Actual Provided	Area per parking (m2)	4-Wheeler	1196	1196	Avg. 33.0	2-Wheeler	1759	1759	Avg. 3.5	Bicycles	1509	1509	Avg. 1.5
Type	Required as per DCR	Actual Provided	Area per parking (m2)																	
4-Wheeler	1196	1196	Avg. 33.0																	
2-Wheeler	1759	1759	Avg. 3.5																	
Bicycles	1509	1509	Avg. 1.5																	
Details of Court cases / litigations w.r.t. the project and project location if any.	NA																			



3. Proposal is an expansion of existing construction project. PP has obtained earlier EC vide letter dated 27.12.2011 for total built up area 69809.87 m<sup>2</sup>. PP has obtained 2nd EC dated 14.05.2018 for Total Built up area 76,236.72m<sup>2</sup> which was amended vide letter dated 13.03.2020 for total built up area 1,67,339.89 m<sup>2</sup>. Proposal has been considered by SEIAA in its 244<sup>th</sup> (Day-3) meeting and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

**Specific Conditions:**

**A. SEAC Conditions-**

1. PP to submit the undertaking regarding baseline data is in valid period & the updated monitoring parameters considered for Traffic, air & noise.
2. PP to submit the note regarding achievement of solar energy saving projected in earlier EC.
3. PP to submit Certified Compliance report from regional office MoEFCC Nagpur.
4. PP to provide minimum 30% of total parking arrangement with electric charging facility by providing charging points at suitable places.
5. PP to ensure that, the water proposed to use for construction phase should not be drinking water. They can use recycled water or tanker water for proposed construction.

**B. SEIAA Conditions-**

1. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
2. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
3. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
4. SEIAA after deliberation decided to grant EC for – FSI- 84399.34 m<sup>2</sup>, Non-FSI- 82556.03 m<sup>2</sup>, Total BUA- 166955.37m<sup>2</sup>. (Plan approval-outward no 761, dated- 08.07.2021).

**General Conditions:**

**a) Construction Phase :-**

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction

workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.

- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to.
- XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XVII. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVIII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- XIX. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
- XX. Regular supervision of the above and other measures for monitoring should be in place

all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

**B) Operation phase:-**

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100% treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.
- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that

the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at [parivesh.nic.in](http://parivesh.nic.in)

- XII. Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
- XIII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIV. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO<sub>2</sub>, NO<sub>x</sub> (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

**C) General EC Conditions:-**

- I. PP has to strictly abide by the conditions stipulated by SEAC & SEIAA.
- II. If applicable "Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered

separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.
5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.
6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.
8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1<sup>st</sup> Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

  
Manisha Patankar-Mhaiskar  
(Member Secretary)

29/6/2022

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Pune.
6. Commissioner, Pune Municipal Corporation
7. Commissioner, PMRDA, Pune
8. Regional Officer, Maharashtra Pollution Control Board, Pune.